

 <p>CIPET लिपेट प्रतिष्ठान - प्रविष्टि - प्रविष्टि</p>	CIPET: SCHOOL FOR ADVANCED RESEARCH IN POLYMERS (SARP) - ARSTPS		
	GOVERNMENT OF INDIA		
	SECTION - I		
	TECHNICAL BID		
e-TENDER No.: CIPET:SARP-ARSTPS/GensetPlatform/e-Ten-05/2020-21			
Description of Work: CONSTRUCTION OF PLATFORM FOR MOUNTING GENERATOR (160KVA)			
Sl. No.	Particulars to be filled-up by the Bidder	Particulars	Remarks, if any
I	Name of the Organization / Contractor		
II	Postal address		
III	Telephone No. with STD code		
IV	Fax with STD code		
V	Name of Contact person		
VI	Mobile No.		
VII	e-mail ID		
	BELOW GIVEN DOCUMENTS TO BE SCANNED AND UPLOADED IN THE WEBSITE www.tenderwizard.com/CIPET WITHIN THE PERIOD OF SUBMISSION.		
1	Certificates:		
	i) PAN (Permanent Account Number) Registration		
	ii) Certificates of GST		
	iii) MSME Certificate, if applicable		
	iv) Two years Experience of executing similar work (enclose proof)		
	v) Satisfactory completion of minimum 02 works of similar nature, value of each contract should be minimum of Rs.3.00 lacs each.		
	Commercial Terms for Quoted items (Please Provide Commercial terms and conditions in the below form)		
2	Validity of offer		
3	The Commercial quote should be INR only		
4	Terms of Payments :- 97% payment will be released on successful completion of the work and 3% will be released after the defect liability period. Agreed / Not Agreed		
5	Work Completion period (in days)		
6	Whether All Documents Relating to tender Viewed		
7	Is there any deviation from the specifications mentioned in the Scope of Work - Yes / No		

<div>  <div> CIPET: SCHOOL FOR ADVANCED RESEARCH IN POLYMERS (SARP) - ARSTPS GOVERNMENT OF INDIA SECTION - I TECHNICAL BID </div>  </div>			
TECHNICAL SPECIFICATIONS (e-TENDER No. CIPET:SARP-ARSTPS/GensetPlatform/e-Ten-05/2020-21)			
S. No	CIPET Specifications	Quantity / Unit (Approx.)	BIDDERS SPECIFICATIONS / REMARKS
1	Earth work in excavation in all kinds of soil in foundation and plinth including disposal of excavated earth away from the soil within a lead of 50 mtrs and lift upto 1.50 mtr.	11 CUM	
2	Excavating supplying and filling of local earth including royalty by mechanical transport upto a lead of 5 km also including ramming, watering of the earth in layers not exceeding 20 cm in foundation and plinth.	8 CUM	
3	Providing and laying cement concrete 1:5:10 in foundation and plinth including watering, ramming and consolidation etc. – complete	4 CUM	
4	Brick work in foundation and plinth in cement mortar 1:6	10 CUM	
5	Providing reinforcement including cutting, bending and placing in position etc. – complete	200 kg.	
6	Providing and laying cement concrete 1:1.5:3 including centering, shuttering, watering, vibrating etc. – complete	2 CUM	
7	Plastering, Brick masonry in cement mortar 1:6	14 SQM	
8	Finishing walls with Acrylic smooth paint of required shade (two or more coats) including a coat of primer	14 SQM	
9	Miscellaneous work such as removing the existing pavement block and disposing within a lead of 50 mtr.	LS	