



CIPET: SARP-LARPM

Department of Chemicals and Petrochemicals, Ministry of Chemicals & Fertilizers, (Govt. of India)

B/25, CNI Complex, (P.O.) KIIT, Patia, Bhubaneswar, Odisha 751024

Ph. No: 0674 2742852, 2740173 Fax No: 0674 2740463

Web: www.larpm.gov.in e-mail: larpm@cipet.gov.in, larpmcipet@larpm.in

Vendor Details

SI. No.	Particulars	
1	Name of The Contractor:	
2	Type of Contractor:	
3	Registered Address & Communication Address:	
4	Branch Address (If any):	
5	Name Of The Contact Person along with Contact No.:	
6	Email ID:	
7	PAN No.: (Please Copy Enclosed)	
8	GST No.: (Please Copy Enclosed)	
9	Major Work Deals (Plz. Specify):	
10	Copy of ITR Certificate for the last three (03) assessment year:	

Date :
Place :

Signature of Bidder
With Seal



Financial Bid

A) Electrical Wiring Of Workstations

Sl. No.	Particulars	Unit	Qty.	Price in Rs.
01	Wiring for light point/fan point/exhaust fan point/call bell point with 1.5 sq. mm FRLSH PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq. mm. FRLSH PVC insulated copper conductor single core cable etc. as required. The cost is exclusive of wires/cables.	Point	30 nos.	
02	Wiring fir circuit/sub main wiring along with earth wire with the following sizes of FRLSH PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required. The cost inclusive of all concealed, cutting, filling and in all proper finish in walls/floors, The cost is exclusive of wires/cables.	Mtr.	800	
03	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FRLSH PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required. The cost inclusive of all concealed, cuttings, filling and in all proper finish in walls or floors. The cost is exclusive of wires/cables. (Cable : 2 X 4.5 sq.mm. + 1 X 2.5 sq. mm)	Mtr.	25	
04	Supplying, testing and fixing suitable size GI/surface box with modular plate and cover in front on surface or in recess, including providing and fixing 2 nos. 3 pin 5/6 A modular socket outlet and 2 nos. 5/6 . A modular switch, connections etc. as required all sanding, filling in all finish. (Make : Legrand/Hager/Anchor/L&T/Crabtree/Similar)	Mtr.	50	
05	Supplying, testing and fixing suitable size GI/surface box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 . A modular socket outlet and 15/16 a modular switch, connections etc switch, connection s etc. as required. The cost inclusive of all sanding, filling in all finish. (Make : Legrand/Hager/Anchor/L&T/Crabtree/Similar)	Mtr.	04	
06	Installation of CAT 6 cable in surface . The cost inclusive of all concealed, cuttings, filling and in all proper finish in walls/floors.	Mtr.	1000	
07	Re-fitting of existing dismantled switches, sockets, plates and covers on wall/ply with necessary screws etc.	Lump sum	--	
08	Re-fixing of existing lights in bathroom and lobby area including its testing and fittings	Nos.	15	
Total Amount (in Rs.)				

For further technical clarification feel free to contact -9424188658

* Payment terms & conditions if any.

Taxes: _____

Work Execution Time: _____

Payment Condition: _____

Validity of Quotation: _____

Any Other :
(Plz Mention)

Date:
Place:

Signature of Bidder
With Seal